

Rezba - Master Bath Remodel & Master Bedroom

Professional Quote

QUOTE

Reference

20260624-CPVUA

Date

June 24, 2026

Valid Until

July 24, 2026

Quote For

Carol & Richard Rezba

4322 Blue Heron Dr., Ponte Vedra Beach, FL 32082
8048394144

From

TolaTiles Inc

445 Hutchinson Ln, St. Augustine, FL 32095, United States
Meni Tola
contact@tolatiles.com
+1 904-866-1738

Summary

Installation of new vent 550 floor, 45 shower floor, 170 wall tile.

Products & Services

Description	Qty	Unit Price	Amount
DEMO - Remove Existing Carpet	1	\$385.00	\$385.00

DEMO - Remove Tub and Existing Tile	1	\$825.00	\$825.00
DEMO - Small Closet, Shower, ceiling, vanity, and closet doors. Demolish small closet next to vanity. Close off door to corner shower. Demolish Tray Cieling. Remove 2 closet doors. Remove Vanity.	1	\$715.00	\$715.00
Remove and Re-install Toilet	1	\$420.00	\$420.00
Plumbing Relocate valve and head piping for the shower. Add a rain shower. Close off pipes in corner shower. connect piping to new vanity	1	\$4200.00	\$4200.00
Install - Waterproofing Installation of kerdi board shower kits and waterproofing. Materials and labor	1	\$1650.00	\$1650.00
Closet Doors Installation of new closet doors. Includes purchasing doors in the price.	1	\$640.00	\$640.00
Electrical Work Install new outlets for vanity. Remove old outlets. Run wire for 2 new vanity lights (one above each mirror). Relocate light on shower cieling.	1	\$2550.00	\$2550.00
Install - Shower Floor Zero Entry Build mud Base shower floor with zero entry (no curb). Includes installation of shower floor tile.	1	\$2100.00	\$2100.00
Install - Shower Wall Tiles Price shown is based off of small to medium tiles (up to 12"x"24inch tile)	1	\$4300.00	\$4300.00
Install - Floor Tiles labor for installation of floor tile throughout bathroom and master bedroom	1	\$4200.00	\$4200.00

Materials - Wedges & Spacers			
(https://www.flooranddecor.com/raimondi-rls-hd-level-clips-1-8in.---2200-count-100983873.html?region_id=SL196&utm_content=	1	\$190.00	\$190.00
Thinset (25 bags)			
https://www.flooranddecor.com/tile-mortars-and-thinsets-installation-materials/mapei-keraflex-super-white-mortar-100893585.html?region=	25	\$35.00	\$875.00
Schluter Metal - 10 pieces			
Tile Trim - https://www.flooranddecor.com/schluter-installation-materials/schluter-jolly-edge-trim-1-2in.-x-10ft.-textured-color-coated-aluminum-matte-v	10	\$35.00	\$350.00
Countertop			
Countertop with two sinks for vanity. Includes the purchase of countertop material and installation. Price may vary based on countertop selection. Price for installation is typically \$35/sqft and estimating \$65/sqft on countertop..	1	\$1700.00	\$1700.00
Custom shower glass door			
Fabrication and installation of custom shower glass door. Includes all materials (glass, accessories, handles, frames, etc.)	1	\$1700.00	\$1700.00
Baseboards			
Installation of new baseboards. 6 inch baseboards. Baseboard material and labor included.	1	\$1000.00	\$1000.00
Ceiling			
Redo ceiling. Flat/Smooth ceiling. 1/4" overboarding. Paint white.	1	\$1100.00	\$1100.00
Installation of new patio door			
Installation of patio door in the master bedroom. Materials included, customer only needs to provide the glass door.	1	\$600.00	\$600.00
Subtotal			\$29500.00
Total			\$29500.00

Terms & Conditions

- Quote valid for 30 days from the date issued.
- Final payment is due upon completion.
- All prices include materials and labor unless otherwise noted.

Questions? Contact Us

Meni Tola

contact@tolatiles.com | +1 904-866-1738

TolaTiles Inc | 445 Hutchinson Ln, St. Augustine, FL 32095, United States