

Bathroom #1

Professional Quote

QUOTE

Reference

20260328-ZDJYW

Date

March 27, 2026

Valid Until

April 27, 2026

Quote For

Natalie Hyder

7038 Waikiki Rd
850-508-5387
nlc06d@gmail.com

From

TolaTiles Inc

445 Hutchinson Ln, St. Augustine, FL 32095, United States
Meni Tola
contact@tolatiles.com
+1 904-866-1738

Summary

Owner-Furnished Materials: The customer will supply tile, grout, vanity, and shower fixtures. Tola Tiles will coordinate and perform pickup of the tile and vanity at no additional cost. Note: Customer should provide approximately 170 sq ft of wall tile and 60 sq ft of floor tile. Demolition & Disposal: Tola Tiles will perform demolition of existing floor and wall tile surfaces. All debris removal and disposal will be handled by Tola Tiles. Substrate Preparation: This proposal includes installation of cement backer board (Hardie Board) at the bathroom floor to provide a stable substrate and reduce the risk of tile movement and cracking. Waterproofing: Applicable wet areas will be properly prepared and waterproofed in accordance with industry standards prior to tile installation. Tile Installation: Installation of new wall and floor tile, including proper setting, alignment, and spacing in accordance with standard tile installation practices. Vanity Installation: Installation and placement of the owner-supplied vanity.

Products & Services

Description	Qty	Unit Price	Amount
Demolition of Existing Wall Tiles Demolition of existing wall tiles and existing hardie boards	1	\$780.00	\$780.00
Demoliton of floor tiles and vanity	1	\$550.00	\$550.00
Installation of Hardie Board and waterproofing	1	\$480.00	\$480.00
Plumbing Relocate shower water valve to meet ADA guidelines, install / relocate shower head, install new faucet in vanity	1	\$650.00	\$650.00
Installation of new wall tiles	1	\$3500.00	\$3500.00
Installation of new floor tiles	1	\$600.00	\$600.00
Installation of new vanity	1	\$350.00	\$350.00
Thinset (6 bags)	6	\$35.00	\$210.00
Foam board waterproofing (11 pieces)	11	\$35.00	\$385.00
Schluter metal (6 pieces) Material for tile edges	6	\$39.00	\$234.00
Remove and Reinstall toilet	1	\$180.00	\$180.00

Build niche above shower	1	\$220.00	\$220.00
Subtotal			\$8139.00
Total			\$8139.00

Terms & Conditions

- Quote valid for 30 days from the date issued.
- Final payment is due upon completion.
- All prices include materials and labor unless otherwise noted.
- Subfloor replacement is not included in the base scope of work. Based on the initial inspection, full replacement is not anticipated. However, if subfloor damage is discovered during demolition, repairs will be performed as needed. Any subfloor work will be billed additionally, not to exceed \$500 for the entire bathroom, inclusive of materials and labor.

Questions? Contact Us

Meni Tola

contact@tolatiles.com | +1 904-866-1738

TolaTiles Inc | 445 Hutchinson Ln, St. Augustine, FL 32095, United States