

Full Bathroom Renovation

Professional Quote

QUOTE

Reference

20260405-Q99M1

Date

April 05, 2026

Valid Until

May 05, 2026

Quote For

Gera Aselton

12464 N Windy Willows Dr

402-430-5269

From

TolaTiles Inc

445 Hutchinson Ln, St. Augustine, FL 32095, United States

Meni Tola

contact@tolatiles.com

+1 904-866-1738

Summary

Project Overview: Full bathroom remodel including demolition, waterproofing, tile installation, plumbing rough-in, and finish work. Customer is responsible for supplying tile, grout, new tub, and fixtures. Tola Tiles will supply the vanity and all remaining materials, and will perform all labor

Demolition & Removal: Full demolition of existing bathroom walls. Removal of existing floor tile, tub, two cabinets, and toilet. Removal of popcorn ceiling. All debris hauled and dumped off-site.

Framing & Substrate: Installation of drywall on exterior shower walls and hardiboard on interior shower surfaces to create a proper waterproof substrate.

Waterproofing: Full waterproofing system installed inside the shower, including all materials and labor.

Plumbing: Installation of new shower valve, shower head, and two faucets for the vanity. Drain relocated for free-standing tub.

Tile Installation: New wall tile installed inside the shower running floor to ceiling, and wrapped 4 feet around the exterior bathroom walls. New floor tile installed throughout. Corner seat and two marble sills installed, one at the shower curb and one at the corner seat.

Shower Pan: New mud pan installed, including all materials and labor.

Vanity: Two new vanities purchased and installed by Tola Tiles.

Accessories: Corner seat and marble sill materials fabricated and installed.

What the Customer Supplies Tile (wall and floor) Grout Fixtures (faucets, shower head, etc.) New Tub

What Tola Tiles Supplies Vanity units (x2) Drywall (5 sheets) Duro Rock / cement board (12 pieces) Thinset (10 bags) Schluter metal tile trim (12 pieces) All waterproofing materials All labor

Products & Services

Description	Qty	Unit Price	Amount
Wall Demolition Demolition of Walls for the whole bathroom.	1	\$1850.00	\$1850.00
Floor Demolition Removal of existing floor tiles	1	\$650.00	\$650.00
Tub Demolition	1	\$650.00	\$650.00
Removal of all debris Cost for loading and hauling waste away	1	\$650.00	\$650.00
Drywall Installation Installation of new drywall outside the bathroom. Lower cost due to whole bathroom already being demoed (less obstruction). *Painting is not included in this line item. The cost of painting is included in the "painting the whole bathroom" below	1	\$1175.00	\$1175.00
Remove popcorn ceiling	1	\$380.00	\$380.00
Waterproofing Installation of water proofing inside the shower (materials and labor)	1	\$250.00	\$250.00
Installation of new wall tiles Includes installation of tiles outside the shower, and wall tiles outside of the bathroom	1	\$3900.00	\$3900.00
Installation of Vanaties Tola tiles will purchase and install the new vanities.	2	\$670.00	\$1340.00
New shower floor Installation of new mud pan, and shower floor	1	\$750.00	\$750.00

New floor tiles			
Installation of new floor tiles for the bathroom	1	\$900.00	\$900.00
Shower Corner Seat			
Installation of corner seat in the shower. This price includes the marble sills for both the corner sill and shower curb.	1	\$350.00	\$350.00
Plumbing			
Plumbing labor - Installation of : new water valve, shower head, 2 faucets (one on each vanity). Relocate valve for free standing tub. Customer will supply fixtures. All other materials and labor covered in the cost.	1	\$2900.00	\$2900.00
Drywall and Duro Rock			
5 pieces of drywall and 12 pieces of DuroRock	17	\$25.00	\$425.00
Thinset			
	10	\$35.00	\$350.00
Schluter Metal			
metal for tile edges (12 pieces)	12	\$39.00	\$468.00
Painting - Whole Bathroom			
Painting the cieling and the walls . This price includes all materials and labors for painting.	1	\$850.00	\$850.00
New Toilet			
New toilet installation. Includes the price of purchasing a new toilet.	1	\$450.00	\$450.00
Glass Sliding door			
Glass Sliding Door - Purchasing and Installing new shower glass sliding door.	1	\$1500.00	\$1500.00
	Subtotal		\$19788.00
	Total		\$19788.00

Terms & Conditions

- Quote valid for 30 days from the date issued.
- Final payment is due upon completion.
- All prices include materials and labor unless otherwise noted.

Questions? Contact Us

Meni Tola

contact@tolatiles.com | +1 904-866-1738

TolaTiles Inc | 445 Hutchinson Ln, St. Augustine, FL 32095, United States
