

Full Bathroom Remodel - Revised

Professional Quote

QUOTE

Reference

20260511-QWMP9

Date

May 11, 2026

Valid Until

June 10, 2026

Quote For

Natalie Hyder

7038 Waikiki Rd

850-508-5387

nlc06d@gmail.com

From

TolaTiles Inc

445 Hutchinson Ln, St. Augustine, FL 32095, United States

Meni Tola

contact@tolatiles.com

+1 904-866-1738

Summary

Bathroom#1 - Main Bathroom with Tub Bathroom#2 - Additional bathroom with walk in shower. Owner-Furnished Materials: The customer will supply tile, grout, vanity, and shower fixtures. Tola Tiles will coordinate and perform pickup of the tile and vanity at no additional cost. All other materials are covered in the quoted prices below. Tile amounts to purchase: 195 sq. ft of wall tile. 60 sqft of floor tile for the bathroom. 25 sqft of floor tile for the shower and niche. Bathroom #1 Scope of work: Demolition & Disposal: Tola Tiles will perform demolition of existing floor and wall tile surfaces. All debris removal and disposal will be handled by Tola Tiles. Substrate Preparation: This proposal includes installation of cement backer board (Hardie Board) at the bathroom floor to provide a stable substrate and reduce the risk of tile movement and cracking. Waterproofing: Applicable wet areas will be properly prepared and waterproofed in accordance with industry standards prior to tile installation. Tile Installation: Installation of new wall and floor tile, including proper setting, alignment, and spacing in accordance with standard tile installation practices. Walls outside of the bathtub will have drywall installed. Vanity Installation: Installation and placement of the owner-supplied vanity. Bathroom #2 Scope of work: Demolition — Remove existing floor, wall tile, and vanity; haul away all debris. Plumbing — Relocate drain lines for the toilet, shower, and vanity. Relocate water valve, water line, and shower head to accommodate the new layout. Walk-In Shower

Construction — Install Hardie board substrate and Schluter-Kerdi waterproofing membrane; build a new shower mud pan. Tile Installation — Install new wall for shower and floor tile throughout bathroom #2, including new Hardie board, closing off the doorway connecting to bathroom #1, and putting up new drywall for the walls. Materials — Includes thinset, foam board waterproofing, and Schluter metal trim for tile edges. Fixture Reinstallation — Reinstall vanity and toilet in updated positions, relocating the vanity closer to the door to create clearance for the new walk-in shower. Note:

Products & Services

Description	Qty	Unit Price	Amount
BATH #1 - Demolition demolition and removal of existing wall tiles, floor tiles, and vanity . This price also includes removeing the toilet and reinstalling the toilet after the job is complete (\$180)	1	\$1510.00	\$1510.00
BATH #1 - Wall Preperation Installation of hardie board and waterproofing around the shower.	1	\$480.00	\$480.00
BATH #1 - Wall Tile Installation This item includes \$220 for building the niche above the bathtub.	1	\$2720.00	\$2720.00
BATH #1 - New Walls outside Bathtub	1	\$1000.00	\$1000.00
BATH #1 - Installation of new floor tiles	1	\$600.00	\$600.00
BATH #1 - Installation of new vanity	1	\$350.00	\$350.00
BATH #1 - Materials (QTY 6) bags of thinset - \$210, (QTY 11) foam waterproofing boards (\$385), (QTY 6) Schluter metal tile edges - \$236	1	\$829.00	\$829.00

BATH #1 - Plumbing	1	\$650.00	\$650.00
BATH #2 - Demolition Remove existing floor, walls, vanity, and take out debris	1	\$1450.00	\$1450.00
BATH #2 - Plumbing Relocate drain for toilet, shower, and vanity. Relocate water valve for the shower, water line, and shower head.	1	\$2900.00	\$2900.00
BATH #2 - Building Walk-in Shower Installation of hardie board in the shower, Schluter-Kerdi waterproofing membrane, and building a shower mud pan	1	\$3000.00	\$3000.00
BATH #2 - Tile Installation Installation of new wall tile in the shower and floor tile for bathroom #2. This includes the cost of re-installing new hardie board, closing up the doorway from bathroom #1, and setting the new tile on the wall.	1	\$2900.00	\$2900.00
BATH #2 - Walls outside shower After tile demolition, the walls outside the shower will be redone with new drywall and painted.	1	\$1000.00	\$1000.00
BATH #2 - Vanity and Toilet	1	\$550.00	\$550.00
BATH #2 - Materials Thinset 6 bags - \$210, Schluter Metal edges 7 pieces (\$273), Foam board waterproofing 15 boards (\$525)	1	\$1008.00	\$1008.00
Subtotal			\$20947.00
Discount (5%)			-\$1047.35

Total

\$19899 . 65

Terms & Conditions

- Quote valid for 30 days from the date issued.
- All prices include materials and labor unless otherwise noted.

Questions? Contact Us

Meni Tola

contact@tolatiles.com | +1 904-866-1738

TolaTiles Inc | 445 Hutchinson Ln, St. Augustine, FL 32095, United States